
# HEMLOCK RIDGE PARK - NEW PAVILION LAKE METROPARKS

5800 VROOMAN ROAD LEROY TOWNSHIP, OH 44077





PROJECT PARCEL DATA LEROY TOWNSHIP, OHIO 44077 PARCEL # 07A-027-009 PARCEL ÄREA 224.820 ACRES

LAND SURVEY NOTES LAND SURVEY DATA SHOWN ON THE CIVIL PLAN SHEETS HAS BEEN REFERENCED FROM A BOUNDARY AND TOPOGRAPHIC FIELD SURVEY PERFORMED BY WILLIAM C. VONDRA OF LAND DESIGN CONSULTANTS.

DATED: 10/17/23 & 10/07/24

DISTURBED AREA 0.47 ACRES

<u>CIVIL ENGINEER</u> ROCKAWAY CIVIL LLC 10191 SPERRY ROAD KIRTLAND, OHIO 44094 JOHN URBANICK, PE 66506 440 655 8182 JURBANICK@ROCKAWAYCIVIL.COM

CONTRACT #: LAKEP1-2303

<u>CIVIL SHEET INDEX</u> C100 COVER SHEET & PROJECT AREA CONTEXT MAP

C101 SITE PLAN & ABBR. SWP3 C102 ABBR. SWP3 DETAILS

INTERFERENCE WITH TRAFFIC:

1. THE CONTRACTOR SHALL MAINTAIN
SAFE TRAFFIC CONDITIONS IN

ACCORDANCE WITH THE MANUAL OF

TRAFFIC CONTROL DEVICES.

COORDINATE ALL LANE / ROAD CLOSURES WITH THE LOCAL

CLEARLY MARKED BY CONES,

TEMPORARY GUARDRAIL. IF THE

MARKERS ARE LEFT IN PLACE AT

ONE WAY TRAFFIC:
3. WHENEVER ONE—WAY TRAFFIC IS

ESTABLISHED, AT LEAST TWO FLAGGERS SHALL BE USED.

THE STREET TO THROUGH TRAFFIC.

PROPER PROVISION FOR TRAFFIC

CONTROL IS NOT BEING PROVIDED,

NECESSARY STEPS TO CORRECT TRAFFIC MAINTENANCE. THE COST OF SUCH SERVICE WILL BE

CHARGED TO THE CONTRACTOR.

THE MUNICIPALITY MAY TAKE

STREET CLOSING: 4. THE CONTRACTOR MAY NOT CLOSE

MAINTENANCE: 5. IF PROPER MAINTENANCE OF TRAFFIC FACILITIES AND/OR

PROVIDED AND MAINTAINED.

NIGHT, SUITABLE LIGHTS SHALL BE

DRUMS, BARRICADES OR

MUNICIPAL ENGINEER(S).

. ALL CONSTRUCTION AND MATERIALS INCLUDED ON THIS PROJECT SHALL BE IN ACCORDANCE WITH THE LATEST STATE OF OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIALS SPECIFICATIONS. 2. ANY DEFECTS IN THE CONSTRUCTION WITHIN THE RIGHT OF WAY INCLUDING MATERIALS OR WORKMANSHIP SHALL BE REPLACED OR CORRECTED BY REMOVAL AND REPLACEMENT BY THE CONTRACTOR OR OTHER APPROVED METHODS PRIOR TO ACCEPTANCE BY THE MUNICIPAL ENGINEER AT 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO ROAD SURFACES, SIGNS, GUARDRAILS, MAIL/PAPER BOXES, CULVERTS, EASEMENTS OR RIGHT OF WAYS DISTURBED BY CONSTRUCTION OF ANY PART OF THIS IMPROVEMENT. ALL DAMAGES SHALL BE RESTORED AT NO COST TO THE MUNICIPALITY TO THE ORIGINAL CONDITION. THE MUNICIPAL ENGINEER IN WRITING SHALL ACCEPT APPROVAL OF RESTORATION. 4. THE CONTRACTOR SHALL NOT COMMENCE WITH ANY FORM OF CONSTRUCTION WITHOUT NOTIFYING THE OFFICE OF THE MUNICIPAL ENGINEER AT LEAST TWENTY-FOUR (24) HOURS PRIOR TO STARTING CONSTRUCTION.

5. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS. DIVERT TRAFFIC FROM ITS NORMAL 6. THE CONTRACTOR SHALL PROVIDE A TWENTY-FOUR (24) HOUR, SEVEN DAYS A WEEK EMERGENCY CONTACT LIST. THE CONTACT LIST SHALL INCLUDE CONTACT NAMES AND PHONE NUMBERS OF INDIVIDUALS WHO CAN BE REACHED AT ANY TIME. NO CONSTRUCTION SHALL OCCUR 7. ALL LAWN AREAS REMOVED OR DISTURBED SHALL BE REPLACED BY SEEDING AND MULCHING IN ACCORDANCE WITH ITEM 659 OF ODOT SPECIFICATIONS AND SHALL BE RESEEDED AND MULCHED WHEN REQUESTED IF SATISFACTORY RE-ESTABLISHMENT OF LAWN DOES NOT OCCUR. 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO THE EXISTING PUBLIC WATER, STORM AND SANITARY SYSTEM RESULTING FROM NON-CONFORMANCE WITH THE APPLICABLE STANDARDS OR THROUGH GENERAL NEGLIGENCE. 9. ALL VOIDS CREATED FROM BORING OF UTILITY LINES SHALL BE BACKFILLED WITH SAND OR GROUT. THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE AT ALL TIMES AND SHALL BACKFILL AND GRADE EXCAVATED AREAS TO ELIMINATE PONDING ON THE SITE.

> <u>DUST CONTROL:</u> 10. THE CONTRACTOR SHALL SUPPLY ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY INCLUDING A DUST-FREE STREET SWEEPING DEVICE OR AS DIRECTED BY THE MUNICIPAL ENGINEER TO MAINTAIN ALL ROADWAYS BEING USED FOR ACCESS TO THE CONSTRUCTION SITE.

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TEMPORARY EROSION CONTROL METHODS IN ACCORDANCE WITH CURRENT COUNTY AND STATE REQUIREMENTS AND AS REQUIRED BY THE MUNICIPAL ENGINEER. EROSION CONTROL MEASURES MUST BE IN PLACE PRIOR TO ANY CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL CLEAN ALL EXISTING STREETS OF MUD AND DIRT DURING THE CONSTRUCTION PHASE AS NEEDED OR DIRECTED BY THE MUNICIPAL ENGINEER.


12. AT ALL STORM SEWER, SANITARY SEWER, AND/OR WATERMAIN INTERSECTIONS HAVING LESS THAN EIGHTEEN (18) INCH VERTICAL SEPARATION, ENCASE THE LOWER AND MONOLITHICALLY CRADLE THE UPPER PIPE IN 3000 PSI CONCRETE PER THE REQUIREMENTS OF THE UNIFORM STANDARDS CONCRETE ENCASEMENT DETAIL.

LINE AND GRADE OF THE LASER SHALL BE "CHECKED" FROM LINE AND GRADE STAKES AT A MAXIMUM OF FIFTY FOOT (50) INTERVALS.

FIELD DATA SHALL INCLUDE MATERIAL TYPE, SIZE, CONDITION, LOCATION, DEPTH / ELEVATION, ETC...

14. WHEREVER UNSTABLE SOIL CONDITIONS ARE ENCOUNTERED THAT ARE NOT INDICATED ON THE PLANS, THE WORK SHALL BE DISCONTINUED UNTIL THE GEOTECHNICAL ENGINEER APPROVES THE METHOD AND MATERIAL TO BE INCORPORATED INTO THE WORK. 15. ALL UNFORESEEN UNDERGROUND OR ABOVE GROUND UTILITIES OR CONDITIONS THAT ARE DISCOVERED IN THE PROJECT AREA DURING CONSTRUCTION SHALL BE REPORTED BY THE CONTRACTOR TO THE DESIGN ENGINEER IMMEDIATELY FOR EVALUATION / POSSIBLE REDESIGN. THE

13. THE LINE AND GRADE OF SEWER MAINS SHALL BE CONTROLLED DURING SEWER CONSTRUCTION BY USE OF AN APPROVED LASER DEVICE. THE



# **DEMOLITION NOTES**

1. TBR = TO BE REMOVED . ETR = EXISTING TO REMAIN

WITH SUITABLE COMPACTED FILL MATERIAL.

- 3. OUPS SHALL BE CONTACTED 2 DAYS PRIOR TO ANY ON SITE EXCAVATION PERFORMED AS PART OF THIS PROJECT 1-800-362-2764.
- 4. THE MOST CURRENT VERSION OF OHIO'S RAINWATER AND LAND DEVELOPMENT MANUAL SHALL BE APPLICABLE TO THIS 5. THE CONTRACTOR SHALL CONDUCT OPERATIONS WITH A MINIMUM INTERFERENCE TO PUBLIC OR PRIVATE
- THOROUGHFARES. MAINTAIN INGRESS EGRESS AND ACCESS AT ALL TIMES. DO NOT CLOSE OR OBSTRUCT ROADWAYS AND SIDEWALKS WITHOUT APPROPRIATE PERMITS. 6. CONTRACTOR IS RESPONSIBLE FOR THE DEMOLITION, REMOVAL, AND DISPOSAL OF ALL STRUCTURES, PADS, WALLS, FOUNDATIONS, PARKING, DRIVES, DRAINAGE STRUCTURES, UTILITIES , ETC..., IN A LOCATION APPROVED BY ALL GOVERNING AGENCIES. ALL ITEMS REMOVED SHALL BE UNDERCUT TO SUITABLE MATERIAL AND BROUGHT TO GRADE

. THE CONTRACTOR IS REQUIRED TO OBTAIN ALL DEMOLITION RELATED PERMITS, INCLUDING AN EPA NOTICE OF INTENT, IF

- 8. THE CONTRACTOR SHALL COORDINATE WITH ALL UTILITY COMPANIES OR DEPARTMENTS PRIOR TO REMOVAL OR SHUTOFF OR INSTALLATION OF ANY UTILITIES. THE CONTRACTOR SHALL COORDINATE WORK WITH THE UTILITY COMPANIES AS TO
- WHICH PORTIONS ARE TO BE PERFORMED BY THE UTILITY COMPANY. 9. CONTRACTOR IS CAUTIONED THAT THE LOCATION AND/ OR ELEVATION OF THE EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANIES AT LEAST 48 HOURS IN ADVANCE OF
- ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF THE UTILITIES 10. EXISTING UTILITIES OR STRUCTURES NOT DESIGNATED FOR REMOVAL ARE TO REMAIN. 11. ALL WASTE OR DEBRIS GENERATED AS PART OF SITE DEMOLITION SHALL BE DISPOSED OF OFF SITE AS PER CURRENT

AGENCY TO BE SUITABLE, SHALL BE USED FOR FILL MATERIAL AS APPROPRIATE.

- GOVERNMENT REGULATIONS. 12. ALL PROJECT AREAS DESIGNATED TO BE PAVED OR BUILT UPON SHALL BE CLEARED AND GRUBBED AS PER PROJECT 13. ANY FILL MATERIAL SALVAGED FROM GRADING OPERATIONS THAT CAN BE DETERMINED BY AN INDEPENDENT TESTING
- 14. ALL EXISTING LANDSCAPING WITHIN THE PROJECT LIMITS SHALL BE REMOVED, EXCEPT AS SHOWN TO REMAIN. TREES BEING REMOVED SHALL HAVE THEIR STUMPS GROUND. 15. CONTRACTOR SHALL MAKE PROVISIONS FOR STORM WATER DURING DEMOLITION PROCESS. 16. ALL STRUCTURES, UTILITIES, ETC.. NOT DESIGNATED FOR REMOVAL SHALL BE PROTECTED BY THE CONTRACTOR DURING
- 17. DEMOLITION SHALL BE PERFORMED WITH CARE AND DUE DILIGENCE AS TO NOT DISRUPT THE OPERATION OF EXISTING UTILITY SERVICES TO REMAIN. ANY UTILITY DISCOVERED DURING DEMOLITION OR CONSTRUCTION, WHICH IS NOT SHOWN
- ON THE PLANS, SHALL BE REPORTED TO THE DESIGN ENGINEER FOR EVALUATION. 18. CONTRACTOR SHALL PROTECT ALL TREES AND LANDSCAPING NOTED TO REMAIN. 19. ALL ITEMS NOTED TO BE SALVAGED ARE TO BE PACKAGED BY THE CONTRACTOR AND TURNED OVER TO THE OWNER
- FOR REUSE. COORDINATE TURNOVER WITH OWNER. 20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION, RELOCATION, AND MAINTENANCE OF ALL EROSION CONTROL AND SEDIMENT PRACTICES 21. OWNER SHALL PROVIDE ABATEMENT RELATED TO ASBESTOS, LEAD CONTAINING MATERIALS, MERCURY, ETC.. AS NEEDED
- PRIOR TO DEMOLITION 22. EXISTING PAVEMENT TYPES SHOWN ARE SURFACE CONDITIONS. DIFFERENT PAVEMENT TYPES MAY EXIST BELOW THE SURFACE. THE COST TO COMPLETELY REMOVE UP TO 12 INCHES OF ALL EXISTING PAVEMENT SECTIONS SHALL BE
- 23. ALL LAWN AREAS REMOVED OR DISTURBED SHALL BE REPLACED BY SEEDING AND MULCHING IN ACCORDANCE WITH ITEM 659 OF ODOT SPECIFICATIONS AND SHALL BE RESEEDED AND MULCHED WHEN REQUESTED IF SATISFACTORY

# SITE PREPARATION AND EARTHWORK NOTES

RE-ESTABLISHMENT OF LAWN DOES NOT OCCUR.

THE RECOMMENDATIONS INCLUDED IN THIS REPORT ARE NOT BASED ON TEST BORINGS, OR ANY KNOWN KNOWLEDGE OF SUBSURFACE CONDITIONS AT THE SITE. ANY FUTURE PROJECT DEVELOPMENT'S EXTENT AND DESIGN ARE UNKNOWN. THE INCLUDED RECOMMENDATIONS MUST BE CONSIDERED PRELIMINARY IN NATURE. ALL RECOMMENDATIONS HAVE BEEN MAINTAINED ON A HIGHLY GENERALIZED PLAN AND ARE NOT TO BE CONSTRUED AS SPECIFIC AND/OR FINALIZED. A DETAILED SITE INVESTIGATION INCLUDING TEST BORINGS, LABORATORY TESTS AND ANALYSIS WILL BE REQUIRED PRIOR TO ANY FINAL DESIGN FOR FUTURE IMPROVEMENTS.

- SITE PREPARATION
  2. PRECAUTIONS SHOULD BE EXERCISED DURING THE REMOVAL OF THE EXISTING BUILDING STRUCTURES AT THE PROPOSED SITE. ALL EXISTING FOUNDATIONS, FLOOR SLABS, BASEMENTS, ETC., SHOULD BE COMPLETELY REMOVED FROM THE SITE. THE EXCAVATIONS SHOULD BE CLEANED OF ALL FOREIGN DEBRIS AND THEN BACKFILLED WITH COMPACTED ENGINEERED FILL MATERIALS TO LESSEN POTENTIAL SETTLEMENT THAT MAY OCCUR. FOLLOWING THE SITE CLEARING, STRIPPING AND UNDERCUTTING, AND PRIOR TO PLACING SUITABLE FILL, THE EXPOSED SUBGRADES SHOULD BE PROOFROLLED WITH A LOADED 20-TON TO 30-TON TANDEM-AXLE DUMP TRUCK UNTIL THE GRADE OFFERS A RELATIVELY UNYIELDING SURFACE. AREAS OF EXCESSIVE YIELDING SHOULD BE EXCAVATED AND BACKFILLED WITH COMPACTED SUITABLE FILL AND/OR THE UNSTABLE SOILS CAN BE STABILIZED BY CHOKING THE EXPOSED BEARING SURFACE WITH CRUSHED LIMESTONE OR SIMILAR COARSE AGGREGATE. AFTER THE EXISTING
- SUBGRADE MATERIALS ARE EXCAVATED PROPER CONTROL OF SUBGRADE COMPACTION AND THE PLACEMENT AND COMPACTION OF NEW FILL MATERIALS SHOULD BE PERFORMED. 4. IT IS RECOMMENDED THAT THE SITE PREPARATION, PROOFROLLING AND EARTHWORK ACTIVITIES SHOULD BE PERFORMED DURING A PERIOD OF DRY WEATHER, WHICH CAN SIGNIFICANTLY REDUCE THE REQUIRED EXTENT OF SOIL STABILIZATION,
- DURING SITE PREPARATION, BURN PITS, TRASH PITS OR OTHER ISOLATED DISPOSAL AREAS MAYBE ENCOUNTERED. ANY SUCH MATERIALS ENCOUNTERED DURING SITE WORK ON CONSTRUCTION SHOULD BE COMPLETELY EXCAVATED AND REMOVED FROM THE SITE.
- SUITABLE FILL

  6. SUITABLE FILL MATERIALS SHOULD CONSIST OF NON-EXPANSIVE MATERIALS, POTENTIALLY EXPANSIVE MATERIALS SHOULD NOT BE USED AS SUITABLE FILL MATERIAL. MATERIALS SELECTED FOR USE AS SUITABLE FILL SHOULD NOT CONTAIN ORGANIC MATTER, WASTE CONSTRUCTION DEBRIS, OR OTHER DELETERIOUS MATERIALS, FILL MATERIALS SHOULD GENERALLY HAVE A STANDARD PROCTOR MAXIMUM DRY DENSITY GREATER THAN 110 POUNDS PER CUBIC FOOT (PCF), AN ATTERBERG LIQUID LIMIT LESS THAN 40, A PLASTICITY INDEX OF LESS THAN 20, AND A MAXIMUM PARTICLE SIZE OF
- REPRESENTATIVE SAMPLES OF THE PROPOSED FILL MATERIAL SHOULD BE COLLECTED AT LEAST ONE WEEK PRIOR TO THE START OF THE FILLING OPERATIONS. THE SAMPLES SHOULD BE TESTED TO DETERMINE THE MAXIMUM DRY DENSITY, OPTIMUM MOISTURE CONTENT, PARTICLE SIZE DISTRIBUTION AND PLASTICITY CHARACTERISTICS. THESE TESTS ARE NEEDED TO DETERMINE IF THE MATERIAL IS ACCEPTABLE AS SUITABLE FILL AND FOR QUALITY CONTROL DURING THE COMPACTION PROCESS.
- 8. THE FILL SHOULD BE PLACED IN LAYERS OF NOT MORE THAN 8 INCHES IN THICKNESS, WITH EACH LAYER BEING COMPACTED TO A MINIMUM DENSITY OF 98 PERCENT OF THE MAXIMUM DRY DENSITY AND WITH +/- 2% OF THE OPTIMUM MOISTURE CONTENT, AS DETERMINED BY THE STANDARD PROCTOR METHOD ASTM D-698. MOISTURE CONTROL OF THE SUITABLE FILL MATERIALS MAY BE NECESSARY FOR COMPACTION.
- 9. SUITABLE FILL OPERATIONS WILL REQUIRE MONITORING/TESTING BY A GEOTECHNICAL CONSULTANT TO ENSURE PROPER COMPACTION REQUIREMENTS ARE MET.
- GROUNDWATER CONTROL AND DRAINAGE

  10. WATER SEEPING MAY BE ENCOUNTERED DURING FOUNDATION EXCAVATION AND DEMOLITION. ACCORDINGLY, A GRAVITY DRAINAGE SYSTEM, SUMP PUMP OR OTHER CONVENTIONAL DEWATERING PROCEDURE AS DEEMED NECESSARY BY THE FIELD CONDITIONS MAY BE NECESSARY. EVERY EFFORT SHOULD BE MADE TO KEEP THE EXCAVATIONS DRY IF WATER IS
- 1. POSITIVE SITE DRAINAGE SHOULD BE PROVIDED TO REDUCE INFILTRATION OF SURFACE WATER AROUND THE PERIMETER OF THE FILL AREA. OVERALL SITE AREA DRAINAGE IS TO BE ARRANGED IN A MANNER SUCH THAT THE POSSIBILITY OF WATER IMPOUNDING OVER THE STRUCTURAL FILL IS PREVENTED.
- 12. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DESIGNING AND CONSTRUCTING STABLE, TEMPORARY EXCAVATIONS AND SHOULD SHORE, SLOPE, OR BENCH THE SIDES OF THE EXCAVATIONS AS REQUIRED TO MAINTAIN STABILITY OF BOTH THE EXCAVATION SIDES AND BOTTOM. THE CONTRACTOR SHOULD EVALUATE THE SOIL EXPOSED IN THE EXCAVATIONS AS PART OF THE CONTRACTOR'S SAFETY PROCEDURES. IN NO CASE SHOULD SLOPE HEIGHT, SLOPE INCLINATION, OR EXCAVATION DEPTH INCLUDING UTILITY TRENCH EXCAVATION DEPTH, EXCEED THOSE SPECIFIED IN LOCAL, STATE AND FEDERAL SAFETY REGULATIONS. 3. MATERIALS REMOVED FROM THE EXCAVATION SHOULD NOT BE STOCKPILED IMMEDIATELY ADJACENT TO THE EXCAVATION,
- 14. THE SOILS COULD BE SENSITIVE TO DISTURBANCES CAUSED BY CONSTRUCTION TRAFFIC AND TO CHANGES IN MOISTURE CONTENT. DURING WET WEATHER PERIODS, INCREASES IN THE MOISTURE CONTENT OF THE SOIL CAN CAUSE SIGNIFICANT REDUCTION IN THE SOIL STRENGTH AND SUPPORT CAPABILITIES. CARE SHOULD BE EXERCISED DURING THE GRADING OPERATIONS AT THE SITE. TRAFFIC OF HEAVY EQUIPMENT, INCLUDING HEAVY COMPACTION EQUIPMENT, MAY VERY WELL CREATE PUMPING AND A GENERAL DETERIORATION OF THE SOILS IN THE PRESENCE OF WATER. THEREFORE, THE GRADING SHOULD, IF AT ALL POSSIBLE, BE PERFORMED DURING A DRY SEASON. A LAYER OF CRUSHED STONE MAY BE REQUIRED TO ALLOW THE MOVEMENT OF CONSTRUCTION TRAFFIC OVER THE SITE DURING THE RAINY SEASON. THE CONTRACTOR SHOULD MAINTAIN POSITIVE SITE DRAINAGE AND IF WET/PUMPING CONDITIONS OCCUR. THE CONTRACTOR WILL BE RESPONSIBLE TO OVER EXCAVATE THE WET SOILS AND REPLACE THEM WITH A PROPERLY

# PAVEMENT DRIVE APRONS, SIDEWALK, CURBS AND CURB RAMP REQUIREMENTS

INASMUCH AS THIS LOAD MAY CAUSE A SUDDEN COLLAPSE OF THE EMBANKMENT.

GENERAL REQUIREMENTS:
THE FOLLOWING REQUIREMENTS APPLY TO ALL PAVEMENT DRIVE APRONS, SIDEWALKS AND CURB RAMPS. ALL PAVEMENT DRIVES, SIDEWALKS AND/OR CURB RAMPS SHALL CONFORM TO ODOT SPECIFICATIONS IF NOT SPECIFIED HEREIN. ALL PAVEMENT DRIVES, SIDEWALKS AND CURB RAMP REPLACEMENTS SHALL CONFORM TO THE GRADE OF THE EXISTING PAVEMENT

1. ALL CONCRETE SHALL BE CLASS "C" PER ODOT 499 AND PROPERLY CONSOLIDATED (NO SLAG).

. THE SCHEDULING FOR WORK SHALL BE DISCUSSED WITH EACH PROPERTY OWNER AFFECTED PRIOR TO COMMENCING THE CONSTRUCTION / REPLACEMENT OPERATION. EXCAVATION IN TRAFFIC AREAS SHALL NOT BE LEFT OPEN OVERNIGHT. ALL DRIVE APRON CONSTRUCTION SHALL FOLLOW A SCHEDULE THAT ALLOWS ACCESS TO AND FROM RESIDENCE, BUSINESS, ETC. AT ALL TIMES. THE DISRUPTION OF ACCESS TO DRIVEWAYS DUE TO THIS WORK SHALL BE KEPT TO A

THE CONTRACTOR MUST PROVIDE ADEQUATE SIGNS, MARKERS AND BARRICADES TO PROTECT PEDESTRIAN TRAFFIC, VEHICULAR TRAFFIC AND CONSTRUCTION PERSONNEL DURING THE PROGRESS OF THIS WORK. ADDITIONAL SIGNS INDICATING ENTRANCES FOR BUSINESSES IN A CONSTRUCTION ZONE ARE REQUIRED AS DIRECTED BY THE MUNICIPAL

4. AN APPROVED SEALER SHALL SEAL ALL EXPOSED CONCRETE APPROPRIATE TO APPLICATION ON SURFACE OF CONCRETE. SEE CURRENT ODOT SPECIFICATIONS FOR APPLICATION METHODS.

5. THE CONTRACTOR SHALL ADJUST ANY "SURFACE STRUCTURE" IN THE AREA OF SIDEWALK AND/OR PAVEMENT DRIVE TO GRADE. THE CONTRACTOR SHALL FURNISH NECESSARY PARTS AND REPAIR ALL "SURFACE STRUCTURES" DAMAGED BY CONSTRUCTION OF IMPROVEMENT.

COMPACTED ENGINEERED FILL.

DRIVE, SIDEWALK AND/OR CURB RAMP.

- 1. IF THE CONTRACTOR BELIEVES THAT SOME OR ALL OF THE EXISTING INFORMATION SHOWN ON THE PROJECT SURVEY IS INACCURATE, THEN THEY ARE REQUIRED TO HAVE A CERTIFIED SURVEY PERFORMED OF THE PROJECT AREA IN SURVEY WILL BE USED AS THE BASIS FOR CONFIRMING ACCURACY OF THE INFORMATION PROVIDED AS PART OF THE
- CONTRACT DOCUMENTS. . ALL NEW EARTHWORK SHALL BE BLENDED TO MEET EXISTING SITE CONDITIONS WHICH ARE TO REMAIN. GRADED SLOPES ARE SHOWN AT 3:1 MAXIMUM. . ALL PROPOSED LAWN AND HARD SURFACE GRADED AREAS SHALL HAVE POSITIVE SURFACE DRAINAGE TOWARDS STORM DRAINAGE STRUCTURES AND AWAY FROM ALL STRUCTURES WHERE APPLICABLE. CONTRACTOR SHALL CONTACT ENGINEER IF DRAINAGE CONFLICTS ARISE IN FIELD DURING CONSTRUCTION.
- 5. ALL PROPOSED PAVEMENT SHALL HAVE A MINIMUM SURFACE SLOPE OF 1.20% AND A MAXIMUM SURFACE SLOPE OF 5.00% UNLESS OTHERWISE NOTED. 6. CONTRACTOR SHALL CONSTRUCT ALL IMPROVEMENTS SO AS TO MINIMIZE DAMAGE TO PAVED AREAS CALLED TO REMAIN OR PAVED AREAS TO BE MILLED AND RESURFACED. 7. THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE LATEST EDITION OF OHIO'S STANDARDS FOR STORMWATER MANAGEMENT LAND DEVELOPMENT AND URBAN STREAM PROTECTION ENTITLED "RAINWATER AND LAND

4. PROPOSED GRADING SHALL NOT INHIBIT THE SURFACE DRAINAGE FOR ADJOINING PARCELS.

RE-ESTABLISHMENT OF LAWN DOES NOT OCCUR.

- DEVELOPMENT" (LATEST EDITION). 8. ALL GRADED SLOPES GREATER THAN OR EQUAL TO 6:1 SHALL HAVE EROSION CONTROL BLANKETS INSTALLED AS PER PROJECT SPECIFICATIONS
- 9. ALL NEW DRIVEWAY APRONS WITHIN THE PUBLIC RIGHT OF WAY(S) SHALL MAINTAIN ADA ACCESSIBLE ACCESS WHERE THE PUBLIC SIDEWALK CROSSES THE NEW DRIVEWAY APRON. 10. ALL LAWN AREAS REMOVED OR DISTURBED SHALL BE REPLACED BY SEEDING AND MULCHING IN ACCORDANCE WITH ITEM

659 OF ODOT SPECIFICATIONS AND SHALL BE RESEEDED AND MULCHED WHEN REQUESTED IF SATISFACTORY

# ABBR. SWP3-1 KEY NOTE LEGEND (#>

- DA = EARTH DISTURBANCE AREA / CLEARING LIMIT CE = CONSTRUCTION ENTRANCE - UTILIZE NEW STONE ACCESS DRIVEWAY & EXISTING PAVED DRIVE / PARKING AREA BETWEEN VROOMAN RD & PROJECT AREA
- SA = STAGING AREA WC = WASTE CONTAINER AREA
- CW = CONCRETE WASHOUT AREA MS = MATERIAL STOCKPILE AREA - CONFIRM FINAL LOCATION, HEIGHT, LIMITS, ETC. WITH LAKE METROPARKS
- FS = FILTER SOCK EB = EROSION CONTROL BLANKETS - ON ALL DISTURBED SLOPES 6:1 AND STEEPER

# ABBR. SWP3 NOTES

# OHIO EPA NPDES PERMIT IS NOT REQUIRED - PROJECT DISTURBANCE IS LESS THAN 1.0 ACRE

THIS PROJECT WILL CONSIST OF CLEARING / GRUBBING TO ALLOW FOR THE CONSTRUCTION OF A NEW PAVILION, NEW

RESTROOM BUILDING, AND NEW HIKING TRAILS. THE TOTAL SITE AREA IS 224.82 ACRES & THE EXPECTED AREA TO BE DISTURBED WITHIN THAT SITE IS 0.47 ACRES AS PER THE USDA SOIL SURVEY, THE SOIL TYPES FOR MOST OF THE SITE ARE: GoF GOSPORT SILTY CLAY LOAM Lb LOBDELL SILT LOAM PeC2 PIERPONT SILT LOAM

PsB PLATEA SILT LOAM Tg TIOGA LOAM UdD UDORTHENTS


- THIS SITE IS CURRENTLY UNDEVELOPED. NO OTHER PRIOR LAND USES ARE KNOWN. SEE STORM WATER POLLUTION PREVENTION PLAN IMPLEMENTATION SCHEDULE.
- IMMEDIATE RECEIVING STREAM OR SURFACE WATER THE STORM WATER DRAINS TO TRIBUTARIES OF THE GRAND NOT APPLICABLE - NOT A SUBDIVIDED DEVELOPMENT
- 8. THERE ARE NOT STORM WATER DISCHARGES ASSOCIATED WITH DEDICATED ASPHALT OR DEDICATED CONCRETE PLANTS 9. A COPY OF THE PERMIT REQUIREMENTS - OHCOOOOOG IS AVAILABLE ON THE OEPA WEBSITE WWW.OEPA.COM. A COPY
- OF THE PERMIT REQUIREMENTS CAN ALSO BE PROVIDED UPON FORMAL REQUEST TO THE ARCHITECT. 10. SEE COVER SHEET FOR PROJECT INFORMATION.
- THE OPERATOR RESPONSIBLE FOR IMPLEMENTATION OF STORM WATER POLLUTION PREVENTION PLAN:
- NOT KNOWN AT THIS TIME THE CERTIFIED PROFESSIONAL WHO PREPARED THE COMPREHENSIVE STORM WATER MANAGEMENT PLAN AND IS AUTHORIZED TO AMEND SAID PLAN.
- JOHN URBANICK ROCKAWAY CIVIL 10191 SPERRY ROAD KIRTLAND, OH 44094
- JURBANICK@ROCKAWAYCIVIL.COM 13. THE SITE OWNER: SETH OLDHAM - LAKE METROPARKS 11211 SPEAR ROAD
- CONCORD TOWNSHIP, OH 44077 SOLDHAM@LAKEMETROPARKS.COM
- 14. SEE APPENDIX I GRADING AND STABILIZATION ACTIVITIES LOG

DISCOVERY OF THE RELEASE.

- 16. OTHER CONTROLS: • IF SUBSTANCES SUCH AS OIL, DIESEL FUEL, HYDRAULIC FLUID, ANTIFREEZE, ETC. ARE SPILLED, LEAKED, OR RELEASE ONTO SOIL, THE SOIL SHOULD BE DUG UP AND DISPOSED OF AT A LICENSED SANITARY LANDFILL OR OTHER APPROVED PETROLEUM CONTAMINATED SOIL REMEDIATION FACILITY (NOT A
  - CONSTRUCTION/DEMOLITION DEBRIS LANDFILL). • SPILLS ON PAVEMENT SHALL BE ABSORBED WITH SAWDUST, KITTY LITTER, OR OTHER ABSORBENT MATERIAL & DISPOSED OF WITH THE TRASH AT A LICENSED SANITARY LANDFILL. • HAZARDOUS OR INDUSTRIAL WASTES SUCH AS MOST SOLVENTS, GASOLINE, OIL-BASED PAINTS, AND CEMENT CURING COMPOUNDS REQUIRE SPECIAL HANDLING. • LARGE PETROLEUM SPILLS (>25 GALLONS) SHALL BE REPORTED TO THE OHIO EPA (1-800-282-9378), LOCAL FIRE DEPARTMENT, AND THE LOCAL EMERGENCY PLANNING COMMITTEE WITHIN 30 MINUTES OF THE
- 19. PROJECT DATES (APPROXIMATE): START DATE APR 2025 END DATE DEC 2025


# SITE PLAN NOTES


- I. REFERENCE PLANS BY OTHERS FOR THE FOLLOWING:
- -EXACT PAVILION FOUNDATION SPECIFICATIONS AND DIMENSIONS (DIMENSIONS SHOWN ARE FOR REFERENCE ONLY) -SITE LIGHTING / UNDERGROUND ELECTRIC INFORMATION -LANDSCAPING / ORNAMENTAL FENCING / PLANTING DETAILS
- 2. ALL DIMENSIONS (HORIZONTAL AND VERTICAL) SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO FABRICATION AND / OR INSTALLATION
- 3. CONTRACTOR SHALL UTILIZE SIGNS, BARRICADES, FLAGMEN, ETC... DURING CONSTRUCTION TO ENSURE THE SAFETY OF PEDESTRIAN AND VEHICULAR TRAFFIC. ALL TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH ODOT ITEM 107-10 AND 614 AND AS PER ORC 4571.09.




CONCRETE PAVING NOTES 1. PROVIDE EXPANSION JOINTS AT 25' MAX SPACING 2. PROVIDE CONTRACTION JOINTS TO A DEPTH  $\frac{1}{4}$  THICKNESS AT 8' MAX SPACING 3. CONTRACTION JOINTS AT LIMITS OF CONCRETE SHALL BE PERPENDICULAR TO THE EDGES OF THE CONCRETE SURFACES 4. SUBMIT JOINT SPACING PLAN TO LAKE METROPARKS FOR <u>APPROVAL PRIOR TO INSTALLATION.</u>

CONCRETE WALK DETAIL







ALTHOUGH SEDIMENT IS THE PRIMARY POLLUTANT OF CONCERN RESULTING FROM CONSTRUCTION ACTIVITY, OTHER POLLUTANTS NEED TO BE CONSIDERED AS WELL. THESE INCLUDE PETROCHEMICALS: FUEL, OIL AND ASPHALT; AND CONSTRUCTION CHEMICALS AND MATERIALS: PAINTS, SOLVENTS, FERTILIZER, SOIL ADDITIVES, CONCRETE WASH WATER, ETC. ALSO INCLUDED ARE SOLID WASTES AND CONSTRUCTION DEBRIS. KEEPING THESE SUBSTANCES FROM POLLUTING RUNOFF CAN BE ACCOMPLISHED TO A LARGE EXTENT THROUGH GOOD HOUSEKEEPING AND FOLLOWING THE MANUFACTURER'S RECOMMENDATIONS FOR THEIR USE AND DISPOSAL.

CONDITION WHERE PRACTICE APPLIES WASTES GENERATED BY CONSTRUCTION ACTIVITIES (I.E. CONSTRUCTION MATERIALS SUCH AS PAINTS, SOLVENTS, FUELS, CONCRETE, WOOD, ETC.) MUST BE DISPOSED OF IN ACCORDANCE WITH ORC 3734 AND ORC 3714. HAZARDOUS AND TOXIC SUBSTANCES ARE USED ON VIRTUALLY ALL CONSTRUCTION—SITES. GOOD MANAGEMENT OF THESE SUBSTANCES IS ALWAYS NEEDED.

GOOD EROSION AND SEDIMENT CONTROL WILL PREVENT SOME POLLUTANTS IN ADDITION TO SEDIMENT FROM LEAVING THE SITE; HOWEVER, POLLUTANTS CARRIED IN SOLUTION OR AS SURFACE FILMS ON RUNOFF WATER WILL BE CARRIED THROUGH MOST EROSION AND SEDIMENT CONTROL PRACTICES. THESE POLLUTANTS BECOME NEARLY IMPOSSIBLE TO CONTROL ONCE CARRIED OFFSITE IN RUNOFF. ADDING TO THE PROBLEM IS THE FACT THAT CONSTRUCTION WASTES, MANY CONTAINING TOXIC CHEMICALS, ARE ROUTINELY BURIED ON-SITE, DUMPED ON THE GROUND, POURED DOWN A STORM DRAIN, OR DISPOSED OF WITH CONSTRUCTION DEBRIS. SO WHILE TYPICAL EROSION AND SEDIMENT-CONTROL PRACTICES ARE IMPORTANT FOR CONTROLLING OTHER POLLUTANTS, ADDITIONAL PREVENTATIVE MEASURES ARE NEEDED.

REDUCING POLLUTANTS OTHER THAN SEDIMENTS DEPENDS HEAVILY ON CONSTRUCTION PERSONNEL AND HOW THEY CARRY OUT THEIR OPERATIONS. TO HELP FACILITATE THIS, PLANS SHOULD CONTAIN STANDARD NOTES CLEARLY STATING REQUIREMENTS TO CONTRACTORS. I' ALSO MAY BE APPROPRIATE TO INCLUDE REQUIREMENTS FOR SPECIFIC PROVISIONS FOR HAZARDOUS MATERIALS STORAGE, HANDLING AND

EDUCATE CONSTRUCTION PERSONNEL, INCLUDING SUBCONTRACTORS WHO MAY USE OR HANDLE HAZARDOUS OR TOXIC MATERIALS, MAKING THEM AWARE OF THE FOLLOWING GENERAL GUIDELINES:

DISPOSAL AND HANDLING OF HAZARDOUS AND OTHER CONSTRUCTION WASTE

PREVENT SPILLS

 USE PRODUCTS UP FOLLOW LABEL DIRECTIONS FOR DISPOSAL REMOVE LIDS FROM EMPTY BOTTLES AND CANS WHEN DISPOSING IN TRASH

• DON'T POUR INTO WATERWAYS, STORM DRAINS OR ONTO THE GROUND DON'T POUR DOWN THE SINK, FLOOR DRAIN OR SEPTIC TANKS

 DON'T BURY CHEMICALS OR CONTAINERS • DON'T BURN CHEMICALS OR CONTAINERS

DON'T MIX CHEMICALS TOGETHER

RECYCLE WASTES WHENEVER POSSIBLE

WASTE DISPOSAL CONTAINERS SHALL BE PROVIDED FOR THE PROPER COLLECTION OF ALL WASTE MATERIAL INCLUDING CONSTRUCTION DEBRIS, SANITARY GARBAGE, PETROLEUM PRODUCTS AND ANY HAZARDOUS MATERIALS TO BE USED ON-SITE. CONTAINERS SHALL BE COVERED AND NOT LEAKING. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT FACILITIES APPROVED FOR THAT MATERIAL. CONSTRUCTION DEMOLITION AND DEBRIS (CD&D) WASTE MUST BE DISPOSED OF IN ACCORDANCE WITH ORC 3714 AT AN APPROVED OHIO EPA CD&D

NO CONSTRUCTION RELATED WASTE MATERIALS ARE TO BE BURIED ON-SITE. BY EXCEPTION, CLEAN FILL (BRICKS, HARDENED CONCRETE, SOIL) MAY BE UTILIZED IN A WAY THAT DOES NOT ENCROACH UPON NATURAL WETLANDS, STREAMS OR THEIR FLOODPLAINS. FILLING OF STREAM SIDE AREAS IS FILL MAY NOT RESULT IN THE CONTAMINATION OF WATERS OF THE STATE, UNLESS PROHIBITED BY LOCAL ORDINANCE OR ZONING.

4. CONSTRUCTION AND DEMOLITION DEBRIS (CD&D) DISPOSAL. CD&D WASTE MUST BE DISPOSED OF IN ACCORDANCE WITH ORC 3714 AT AN

APPROVED OHIO EPA CD&D LANDFILL. CD&D WASTE IS DEFINED AS ALL MATERIALS ATTACHED TO A STRUCTURE, WHICH IS BEING DEMOLISHED (FOR MATERIALS CONTAINING ASBESTOS SEE ITEM 12). HANDLING CONSTRUCTION CHEMICALS. MIXING, PUMPING, TRANSFERRING OR OTHER HANDLING OF CONSTRUCTION CHEMICALS SUCH AS FERTILIZER, LIME, ASPHALT, CONCRETE DRYING COMPOUNDS, AND ALL OTHER POTENTIALLY HAZARDOUS MATERIALS SHALL BE PERFORMED IN AN AREA AWAY FROM ANY WATERCOURSE, DITCH OR STORM DRAIN. . EQUIPMENT FUELING AND MAINTENANCE, OIL CHANGING, ETC., SHALL BE PERFORMED AWAY FROM WATERCOURSES, DITCHES OR STORM

DRAINS, IN AN AREA DESIGNATED FOR THAT PURPOSE. THE DESIGNATED AREA SHALL BE EQUIPPED FOR RECYCLING OIL AND CATCHING SPILLS. SECONDARY CONTAINMENT SHALL BE PROVIDED FOR ALL FUEL OIL STORAGE TANKS. THESE AREAS MUST BE INSPECTED EVERY SEVEN DAYS AND WITHIN 24 HRS. OF A 0.5 INCH OR GREATER RAIN EVENT TO ENSURE THERE ARE NO EXPOSED MATERIALS WHICH WOULD CONTAMINATE STORM WATER. SITE OPERATORS MUST BE AWARE THAT SPILL PREVENTION CONTROL AND COUNTERMEASURES (SPCC) REQUIREMENTS MAY APPLY. AN SPCC PLAN IS REQUIRED FOR SITES WITH ONE SINGLE ABOVEGROUND TANK OF 660 GALLONS OR MORE, ACCUMULATIVE ABOVEGROUND STORAGE OF 1330 GALLONS OR MORE, OR 42,000 GALLONS OF UNDERGROUND STORAGE. SOILS THAT HAVE BECOME CONTAMINATED MUST BE DISPOSED OF ACCORDANCE WITH ITEM 8 CONTAMINATED SOILS. CONCRETE WASH WATER/WASH OUTS. CONCRETE WASH WATER SHALL NOT BE ALLOWED TO FLOW TO STREAMS, DITCHES, STORM DRAINS, OR ANY OTHER WATER CONVEYANCE. A SUMP OR PIT WITH NO POTENTIAL FOR DISCHARGE SHALL BE CONSTRUCTED IF NEEDED TO

CONTAIN CONCRETE WASH WATER. FIELD TILE OR OTHER SUBSURFACE DRAINAGE STRUCTURES WITHIN 10 FT. OF THE SUMP SHALL BE CUT AND PLUGGED. FOR SMALL PROJECTS. TRUCK CHUTES MAY BE RINSED ON THE LOT AWAY FROM ANY WATER CONVEYANCES. CONTAMINATED SOILS. IF SUBSTANCES SUCH AS OIL, DIESEL FUEL, HYDRAULIC FLUID, ANTIFREEZE, ETC. ARE SPILLED, LEAKED, OR RELEASED ONTO THE SOIL, THE SOIL SHOULD BE DUG UP AND DISPOSED OF AT LICENSED SANITARY LANDFILL OR OTHER APPROVED PETROLEUM CONTAMINATED SOIL REMEDIATION FACILITY (NOT A CONSTRUCTION/DEMOLITION DEBRIS LANDFILL). PLEASE BE AWARE THAT STORM WATER RUNOFF ASSOCIATED WITH CONTAMINATED SOILS ARE NOT AUTHORIZED UNDER OHIO EPA'S GENERAL STORM WATER PERMIT ASSOCIATED WITH CONSTRUCTION ACTIVITIES. IN THE EVENT THERE ARE LARGE EXTENSIVE AREAS OF CONTAMINATED SOILS ADDITIONAL MEASURES ABOVE AND BEYOND THE CONDITIONS OF OHIO EPA'S GENERAL CONSTRUCTION STORM WATER PERMIT WILL BE REQUIRED. DEPENDING ON THE EXTENT OF CONTAMINATION, ADDITIONAL TREATMENT AND/OR COLLECTION AND DISPOSAL MAY BE REQUIRED. ALL STORM WATER DISCHARGES ASSOCIATED WITH THE CONTAMINATED SOILS MUST BE AUTHORIZED UNDER AN ALTERNATE NPDES (NATIONAL

POLLUTANT DISCHARGE ELIMINATION SYSTEM) PERMIT. SPILL REPORTING REQUIREMENTS: SPILLS ON PAVEMENT SHALL BE ABSORBED WITH SAWDUST, KITTY LITTER OR OTHER ABSORBENT MATERIAL AND DISPOSED OF WITH THE TRASH AT A LICENSED SANITARY LANDFILL. HAZARDOUS OR INDUSTRIAL WASTES SUCH AS MOST SOLVENTS, GASOLINE, OIL-BASED PAINTS, AND CEMENT CURING COMPOUNDS REQUIRE SPECIAL HANDLING. SPILLS SHALL BE REPORTED TO OHIO EPA (1-800-282-9378). SPILLS OF 25 GALLONS OR MORE OF PETROLEUM PRODUCTS SHALL BE REPORTED TO OHIO EPA (1-800-282-9378), THE LOCAL FIRE DEPARTMENT, AND THE LOCAL EMERGENCY PLANNING COMMITTEE WITHIN 30 MIN. OF THE DISCOVERY OF THE RELEASE. ALL SPILLS, WHICH RESULT IN CONTACT WITH WATERS OF THE STATE, MUST BE REPORTED TO OHIO EPA'S HOTLINE.

10. OPEN BURNING. NO MATERIALS MAY BE BURNED WHICH CONTAIN RUBBER, GREASE, ASPHALT, OR PETROLEUM PRODUCTS SUCH AS TIRES, CARS, AUTO PARTS, PLASTICS OR PLASTIC COATED WIRE. (SEE OAC 3745-19) OPEN BURNING IS NOT ALLOWED IN RESTRICTED AREAS. RESTRICTED AREAS ARE DEFINED AS: 1) WITHIN CORPORATION LIMITS; 2) WITHIN 1000 FEET OUTSIDE A MUNICIPAL CORPORATION HAVING A POPULATION OF 1000 TO 10,000; AND 3) A ONE MILE ZONE OUTSIDE OF A CORPORATION OF 10,000 OR MORE. OUTSIDE A RESTRICTED AREA, NO OPEN BURNING CAN TAKE PLACE WITHIN A 1000 FEET OF AN INHABITED BUILDING LOCATED OFF THE PROPERTY WHERE THE FIRE IS SET. OPEN BURNING IS PERMISSIBLE IN A RESTRICTED AREA FOR THE FOLLOWING ACTIVITIES: HEATING TAR. WELDING AND ACETYLENE TORCHES, SMUDGE POTS AND SIMILAR OCCUPATIONAL NEEDS, AND HEATING FOR WARMTH OR OUTDOOR BARBEQUES. OUTSIDE OF RESTRICTED AREAS, OPEN BURNING IS PERMISSIBLE FOR LANDSCAPE WASTES (PLANT MATERIAL), LAND-CLEARING WASTES (PLANT MATERIAL, WITH PRIOR WRITTEN PERMISSION FROM OHIO EPA), AND AGRICULTURAL WASTES (MATERIAL GENERATED BY CROP, HORTICULTURAL, OR LIVESTOCK PRODUCTION PRACTICES. THIS INCLUDES FENCE POSTS AND SCRAP LUMBER, BUT NOT BUILDINGS).

1 DUST CONTROL/SUPPRESSANTS. DUST CONTROL IS REQUIRED TO PREVENT NUISANCE CONDITIONS. DUST CONTROLS MUST BE USED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND NOT BE APPLIED IN A MANNER, WHICH WOULD RESULT IN A DISCHARGE TO WATERS OF THE STATE. ISOLATION DISTANCES FROM BRIDGES, CATCH BASINS, AND OTHER DRAINAGEWAYS MUST BE OBSERVED. APPLICATION (EXCLUDING WATER) MAY NOT OCCUR WHEN PRECIPITATION IS IMMINENT AS NOTED IN THE SHORT TERM FORECAST. USED OIL MAY NOT BE APPLIED FOR DUST CONTROL. 12. OTHER AIR PERMITTING REQUIREMENTS: ALL CONTRACTORS AND SUB CONTRACTORS MUST BE MADE AWARE THAT CERTAIN ACTIVITIES ASSOCIATED WITH CONSTRUCTION WILL REQUIRE AIR PERMITS. ACTIVITIES INCLUDING BUT NOT LIMITED TO MOBILE CONCRETE BATCH PLANTS, MOBILE ASPHALT PLANTS, CONCRETE CRUSHERS, LARGE GENERATORS, ETC., WILL REQUIRE SPECIFIC OHIO EPA AIR PERMITS FOR

NOTIFICATION FOR RESTORATION AND DEMOLITION MUST BE SUBMITTED TO OHIO EPA FOR ALL COMMERCIAL SITES TO DETERMINE IF 3. PROCESS WASTE WATER/LEACHATE MANAGEMENT. ALL CONTRACTORS SHALL BE MADE AWARE THAT OHIO EPA'S CONSTRUCTION GENERAL PERMIT ONLY ALLOWS THE DISCHARGE OF STORM WATER. OTHER WASTE STREAMS/DISCHARGES INCLUDING BUT NOT LIMITED TO VEHICLE AND/OR EQUIPMENT WASHING, LEACHATE ASSOCIATED WITH ON-SITE WASTE DISPOSAL, CONCRETE WASH OUTS, ETC. ARE A PROCESS WASTEWATER. THEY ARE NOT AUTHORIZED FOR DISCHARGE UNDER THE GENERAL STORM WATER PERMIT ASSOCIATED WITH CONSTRUCTION ACTIVITIES. ALL PROCESS WASTEWATERS MUST BE COLLECTED AND PROPERLY DISPOSED AT AN APPROVED DISPOSAL FACILITY. IN THE EVENT THERE ARE LEACHATE OUTBREAKS ASSOCIATED WITH ONSITE DISPOSAL. MEASURES MUST BE TAKEN TO ISOLATE THIS DISCHARGE FOR

INSTALLATION AND OPERATION. THESE ACTIVITIES MUST SEEK AUTHORIZATION FROM THE CORRESPONDING DISTRICT OF OHIO EPA.

COLLECTION AND PROPER DISPOSAL. INVESTIGATIVE MEASURES AND CORRECTIVE ACTIONS MUST BE IMPLEMENTED TO IDENTIFY AND ELIMINATE THE SOURCE OF ALL LEACHATE OUTBREAKS. 14. TRENCH AND GROUND WATER CONTROL - NO SEDIMENT LADEN OR TURBID DISCHARGES FROM ARE PERMITTED TO DISCHARGE TO WATER RESOURCES OR WETLANDS. TRENCH OR GROUND WATER CONTAINING SEDIMENT MUST PASS THROUGH A SEDIMENT SETTLING POND OR OTHER EQUALLY EFFECTIVE SEDIMENT CONTROL DEVICE PRIOR TO DISCHARGE. ALTERNATIVELY, SEDIMENT MAY BE REMOVED BY SETTLING IN PLACE OR BY DEWATERING INTO FILTER BAG, SUMP PIT OR EQUALLY EFFECTIVE PRACTICE. GROUND WATER DEWATERING THAT DOES NOT CONTAIN SEDIMENT OR OTHER POLLUTANTS IS NOT REQUIRED TO BE TREATED PRIOR TO DISCHARGE. ENSURE THAT THE NON-SEDIMENT

LADEN GROUND WATER DOES NOT BECOME POLLUTANT LADEN BY FLOWING OVER DISTURBED SOIL OR POLLUTANT SOURCES. 15. PERMIT TO INSTALL (PTI) REQUIREMENTS: ALL CONTRACTORS AND SUB CONTRACTORS MUST BE MADE AWARE THAT A PTI MUST BE SUBMITTED AND APPROVED BY OHIO EPA PRIOR TO THE CONSTRUCTION OF ALL CENTRALIZED SANITARY SYSTEMS, INCLUDING SEWER EXTENSIONS, AND SEWERAGE SYSTEMS (EXCEPT THOSE SERVING ONE, TWO, AND THREE FAMILY DWELLINGS) AND POTABLE WATER LINES. THE ISSUANCE OF AN OHIO EPA CONSTRUCTION GENERAL STORM WATER PERMIT DOES NOT AUTHORIZE THE INSTALLATION OF ANY SEWERAGE SYSTEM WHERE OHIO EPA HAS NOT APPROVED A PTI.

# STORM WATER POLLUTION PREVENTION PLAN IMPLEMENTATION SCHEDULE:

ITEMS LISTED IN THIS IMPLEMENTATION SCHEDULE ARE TO BE ADDRESSED CHRONOLOGICALLY IN THE ORDER THEY ARE LISTED. THIS IMPLEMENTATION SCHEDULE IS TO BE USED AS A GENERAL GUIDE FOR STORM WATER POLLUTION PREVENTION ITEMS. AT A MINIMUM, ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSPECTED AT LEAST ONCE EVERY 7 DAYS AND WITHIN 24 HOURS OF ANY STORM EVENT GREATER THAN 0.5 INCH PER 24 HOUR PERIOD. EROSION AND SEDIMENT CONTROLS THAT ARE FOUND TO BE IN NEED OF REPAIR DURING THE INSPECTION ARE TO BE REPAIRED WITHIN 3 DAYS OF THE INSPECTION.

CONTRACTOR IS TO REVIEW THIS PLAN PRIOR TO INITIATING ANY WORK ON SITE. THE CONTRACTOR IS ALSO RESPONSIBLE FOR REVIEWING

AND OBTAINING AN NPDES PERMIT FROM THE OHIO EPA PRIOR TO INITIALIZATION OF WORK ON THE SITE CONSTRUCTION ACCESS DRIVE SHALL BE LIMITED AS SHOWN ON THE PLANS . ALL VEHICLES ENTERING THE SITE DURING CONSTRUCTION ARE TO USE THIS DRIVE FOR INGRESS AND EGRESS. THIS IS THE ONLY POINT OF INGRESS AND EGRESS TO BE USED DURING THE ENTIRE CONSTRUCTION PROCESS IN ORDER TO REDUCE CONSTRUCTION MATERIALS FROM BEING MOVED ONTO PUBLIC ROADWAYS. THE DRIVE IS TO BE INSPECTED FOR INTEGRITY AT THE END OF EACH DAY. REPAIRS ARE TO BE MADE AND THE DRIVE SHALL BE CLEANED

THE LIMITS OF DISTURBANCE / CLEARING SHALL BE STAKED OUT PRIOR TO THE START OF CONSTRUCTION ACTIVITIES. THE STAGING AREA IS TO BE INSTALLED AT THE LOCATION DEPICTED ON THIS SWPPP. ALL VEHICLES THAT ARE NOT IN USE OR ARE TO REMAIN OVERNIGHT ARE TO BE KEPT IN THE STAGING AREA AND SHALL NOT LIE IDLE IN ANY OTHER AREAS ON SITE. INSTALL THE CONCRETE WASHOUT PIT AND BRING WASTE CONTAINERS TO THE SITE IMMEDIATELY. THE GENERAL CONTRACTOR IS

RESPONSIBLE FOR ENSURING THAT WASTE CONTROL PROCEDURES ARE BEING PERFORMED TO PREVENT POLLUTION INTO THE STORM WATER SYSTEM DURING CONSTRUCTION. CONTRACTOR IS TO INSTALL ALL SEDIMENT AND EROSION CONTROL DEVICES PRIOR TO THE START OF DEMOLITION. EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED WITHIN 7 DAYS OF GRUBBING. THESE ITEMS INCLUDE, BUT ARE NOT LIMITED TO, FILTER SOCKS, SILT FENCE, DANDY BAGS AND INLET PROTECTION. SILT FENCE POSTS ARE TO BE SET A MAXIMUM OF 6' FROM EACH OTHER AND THE ENDS OF THE GEOTEXTILE FABRIC OF THE SILT FENCE ARE TO BE SLOPED TOWARD THE UP SLOPE OF THE AREA IT IS SERVING TO PREVENT RUNOFF FROM GOING AROUND THE ENDS OF THE SILT FENCE. SILT FENCE IS TO BE INSPECTED AT THE BEGINNING OF

THE GEOTEXTILE FABRIC, COLLAPSED POSTS FROM TOO MUCH RUNOFF OF SILT / SOIL, MISDIRECTION OF SEDIMENT DUE TO IMPROPER INSTALLATION OF EROSION, VANDALISM, ETC THE CONTRACTOR MUST INSTALL EROSION CONTROLS AND SEDIMENT CONTROLS INCLUDING, BUT NOT LIMITED TO, FILTER SOCKS, SILT FENCE, DIVERSION BERMS, SEDIMENT TRAPS) AS MORE AREAS BECOME DISTURBED THROUGHOUT CONSTRUCTION. THIS SHALL BE DONE PRIOR TO DISTURBING PREVIOUSLY UNDISTURBED LANDS

EACH DAY AND REPAIRS ARE TO BE MADE IMMEDIATELY. REPAIRS MAY INCLUDE, BUT ARE NOT LIMITED TO THE FOLLOWING: TEARS IN

ALL TRENCH AND GROUND WATER COLLECTED IS TO BE PUMPED INTO THE SEDIMENT TRAP TO BE TREATED FOR WATER QUALITY AND DEWATERING DURING CONSTRUCTION THE SOIL IS TO BE STRIPPED OF ITS TOP ORGANIC LAYER AS NECESSARY ONLY AFTER ALL SEDIMENT AND EROSION CONTROLS HAVE BEEN INSTALLED AND INSPECTED FOR PROPER OPERATION.

10. CLEARING OF THE SITE AND STRIPPING OF EXISTING TOPSOIL WILL BE PERFORMED IN A MANNER THAT DOES NOT DISTURB NEIGHBORING LAND OR PUBLIC ROADWAYS FROM THEIR NORMAL CONDITION. DURING AND AT THE END OF EACH DAY OF TOPSOIL STRIPPING. THE DISTURBED SOIL IS TO BE TREATED WITH OEPA RECOMMENDED DUST SUPPRESSANTS SO THAT DUST DOES NOT ACCUMULATE NOR HAVE. THE ABILITY TO SPREAD ONTO NEIGHBORING PROPERTIES, PUBLIC ROADWAYS, OR INTO STORM SEWER STRUCTURES DURING NORMAL WORKING HOURS.

SURROUNDED BY SILT FENCE OR FILTER SOCK AT THE END OF THE FIRST DAY OF BUILDING OF THE STOCKPILES. IF THE STOCKPILE IS TO REMAIN UNDISTURBED FOR LONGER THAN A PERIOD OF 7 DAYS. THEN TEMPORARY SEEDING MUST BE PERFORMED ON THE STOCKPILE AS PER SPECIFICATIONS OF THE SWPPP. SILT FENCE OR FILTER SOCKS MUST BE PLACED AROUND THE PERIMETER OF THE SOIL STOCKPILE ONCE IT HAS BEEN ESTABLISHED. TEMPORARY SEEDING IS TO TAKE PLACE AS PER THE SPECIFICATIONS DESCRIBED ON THE PLANS. TEMPORARY SEEDING IS TO BE PLACED

IN AREAS THAT WILL REMAIN IDLE FOR LONGER THAN 7 DAYS. 13. CONSTRUCTION VEHICLES USED IN CONCRETE RELATED WORK ARE TO BE CLEANED OFF AT THE CONCRETE WASH OUT AREA AS DEPICTED ON THIS SWPPP. THIS IS TO BE PERFORMED AT THE END OF EACH DAY OF CONCRETE DEMOLITION AND AT THE END OF ENTIRE CONCRETE DEMOLITION PORTION OF PROJECT. IF THE PRIMARY CONCRETE WASH OUT AREA BECOMES TOO HARD AND DOES NOT ALLOW THE CONCRETE WASH OFF TO PROPERLY WASH OUT, THEN A NEW WASH OUT AREA SHALL BE CREATED AND USED FOR CLEANING WHILE THE OTHER WASH OUT AREA IS REPAIRED. 14. ALL EXCAVATED UTILITY TRENCHES MUST BE STABILIZED AT THE END OF EACH DAY WITH GRAVEL BACKFILL FROM THE BOTTOM OF THE

TRENCH TO THE SURFACE TO PREVENT EROSION OF THE TRENCH OVERNIGHT. 15. ALL SPARE AND WASTE CONSTRUCTION MATERIALS ARE TO BE DISPOSED OF IN WASTE CONTAINERS, WHICH ARE TO BE EMPTIED PRIOR TO REACHING THEIR MAXIMUM CAPACITY. SPARE CONSTRUCTION MATERIALS MAY ALSO BE TRANSPORTED OFFSITE TO AN APPROPRIATE LOCATION DETERMINED BY THE CONTRACTOR (I.E. THE CONTRACTOR'S STORAGE WAREHOUSE), OTHERWISE MATERIALS ARE TO BE DISPOSED

OF AT AN OFFSITE CONSTRUCTION AND DEBRIS DEMOLITION LANDFILL AS PER ORC 3714. 16. WHEN TOXIC MATERIALS (I.E. FUEL) ARE USED TO CLEAN THE MACHINERY, THE CLEANING MUST TAKE PLACE ON THE STAGING AREA. THE STAGING AREA MUST BE BARRICADED/BERMED AS TO NOT ALLOW RUNOFF FROM THE STAGING AREA ONTO PERMEABLE AREAS. THE TOXIC RUNOFF FROM CLEANING OF MACHINERY IS TO BE COLLECTED VIA VACUUM AND PLACED INTO BARRELS WHICH ARE TO BE DISPOSED OF OFF SITE AT A CONSTRUCTION AND DEBRIS DEMOLITION LANDFILL AS PER ORC 3714.

HOUR PERIOD.


- TEMPORARY BMPS ARE TO BE INSPECTED WEEKLY AND AFTER EVERY RAIN EVENT OF 0.5 INCHES WITHIN A 24
- 2. AN INSPECTION WAIVER REQUEST IS TO BE SUBMITTED TO THE OEPA TO REDUCE THE AMOUNT OF MONTHLY INSPECTION IF THE SITE IS TO LIE DORMANT FOR AN EXTENDED PERIOD OF TIME. 3. INSPECTIONS ARE TO BE PERFORMED BY "QUALIFIED INSPECTION PERSONNEL." INSPECTION RECORDS ARE TO BE
- KEPT FOR A MINIMUM 3 YEARS AFTER THE TERMINATION OF CONSTRUCTION ACTIVITIES. 4. AN INSPECTION CHECKLIST WILL BE COMPLETED AND SIGNED BY THE INSPECTOR AFTER EVERY INSPECTION.
- 5. NON-SEDIMENT BMPS ARE TO BE REPAIRED WITHIN 3 DAYS OF INSPECTION AND SEDIMENT PONDS ARE TO BE REPAIRED AND CLEANOUT WITHIN 10 DAYS OF INSPECTION. BMPS THAT ARE NOT MEETING THE INTENDED FUNCTION OR HAVE NOT BEEN INSTALLED ARE TO BE REINSTALLED/INSTALLED WITHIN 10 DAYS OF INSPECTION.

# <u>APPENDIX G - SWPPP AMENDMENT LOG</u>

AMENDMENT NUMBER	DESCRIPTION OF THE AMENDMENT	DATE OF AMENDMENT	AMENDMENT PREPARED BY

# <u>APPENDIX I — GRADING AND STABILIZATION ACTIVITIES LOG</u>

SWPPP CONTACT:	SWPPP CONTACT:						
DATE GRADING ACTIVITY INITIATED	DESCRIPTION OF GRADING ACTIVITY	DATE GRADING ACTIVITY CEASED (INDICATE TEMPORARY OR PERMANENT)	DATE STABILIZATION MEASURED INITIATED	DESCRIPTION OF STABILIZATION MEASURE AND LOCATION			



NOTE.									
FEBRUARY 29									
TO	USE	MULCH	ONLY,	SODDING	PRACTICES,	OR	DORMANT	SEEDING.	

# ADDITIONAL TEMPORARY STABILIZATION NOTES:

OTHER APPROVED SEED SPECIES MAY BE APPROVED.

TEMPORARY SEEDING IS REQUIRED FOR ANY AREAS THAT WILL REMAIN IDLE OVER THE WINTER PRIOR TO THE ONSET OF WINTER WEATHER. . TEMPORARY SEEDING IS REQUIRED WITHIN 2 DAYS OF THE MOST RECENT DISTURBANCE FOR AN AREA WITHIN 50 FEET OF A SURFACE WATER OF THE STATE AND NOT AT FINAL GRADE THAT WILL REMAIN IDLE FOR 14 DAYS OR MORE. TEMPORARY SEEDING IS REQUIRED ON ANY DISTURBED AREA, INCLUDING SOIL STOCKPILES

THAT WILL LIE DORMANT FOR MORE THAN 14 DAYS BLIT LESS THAN ONE YEAR AND NOT WITHIN 50 FEET OF A SURFACE WATER OF THE STATE WITHIN 7 DAYS OF THE MOST RECENT

# TEMPORARY SEEDING SPECIFICATIONS


F	PERMANENT SEE	DING SPECIFICATIONS		
CEED MIV	SE	EDING RATE	NOTES	
SEED MIX	LB/ACRE	LB/1,000 FT <sup>2</sup>		
	GENE	ERAL USE		
CREEPING RED FESCUE DOMESTIC RYEGRASS KENTUCKY BLUEGRASS	20-40 10-20 20-40	0.50-1.00 0.25-0.50 0.50-1.00	FOR CLOSE MOWING AND FOR WATERWAYS WITH <2.0 FT/SEC VELOCITY	
TALL FESCUE	40-50	1.00-1.25		
TURF-TYPE (DWARF) FESCUE	90	2.25		
	STEEP BANKS	OR CUT SLOPES		
TALL FESCUE	40-50	1.00-1.25		
CROWN VETCH TALL FESCUE	10-20 20-30	0.25-0.50 0.50-0.75	DO NOT SEED LATER THAN AUGUST	
FLAT PEA TALL FESCUE	20-25 20-30	0.50-0.75 0.50-0.75	DO NOT SEED LATER THAN AUGUST	
	ROAD DITCH	ES AND SWALES		
TALL FESCUE	40-50	1.00-1.25		
TURF-TYPE (DWARF) FESCUE KENTUCKY BLUEGRASS	90 5	2.25 0.10		
	L	AWNS		
KENTUCKY BLUEGRASS PERENNIAL RYEGRASS	100-120	2.00 2.00		
KENTUCKY BLUEGRASS CREEPING RED FESCUE	100-120	2.00 1.50	FOR SHADED AREAS	
NOTE:		<u>'</u>		

# FOLLOWING SOIL TEST RECOMMENDATIONS IS PREFERRED TO FERTILIZER RATES SHOWN ABOVE

# ADDITIONAL PERMANENT SEEDING REQUIREMENTS:

- 1. PERMANENT SEEDING IS REQUIRED FOR ANY DISTURBED AREA THAT WILL LIE DORMANT FOR ONE YEAR OR MORE WITHIN 7 DAYS OF THE MOST RECENT DISTURBANCE. PERMANENT SEEDING IS REQUIRED FOR ANY AREA WITHIN 50 FEET OF A SURFACE WATER
- BODY OF THE STATE AND AT FINAL GRADE WITHIN 2 DAYS OF REACHING FINAL GRADE. 3. PERMANENT SEEDING IS REQUIRED FOR ANY AREA AT FINAL GRADE WITHIN 7 DAYS OF REACHING FINAL GRADE.

# PERMANENT SEEDING SPECIFICATIONS



3. THE MIDPOINT OF THE ROCK CHECK DAM WITHER BY HAND OF MECHANICALLY AS LONG AS

SHALL BE A MINIMUM OF 6 INCHES LOWER THAN THE CENTER OF THE CHECK DAME IS LOWER THE SIDES IN ORDER TO DIRECT ACROSS THE THAN THE SIDES AND EXTENDS ACROSS THE

4. THE BASE OF THE CHECK DAM SHALL BE 8. SIDE SLOPES SHALL BE A MINIMUM OF 2:1.

CENTER AND AWAY FROM THE CHANNEL SIDES. CHANNEL.

7. STONE PLACEMENT SHALL BE PERFORMED

EXCEED 3.0 FEET.

SHOWN ON THE PLANS.

ENTRENCHED APPROXIMATELY 6 INCHES.

5. SPACING OF CHECK DAMS SHALL BE IN A

MANNER SUCH THAT THE TOP OF THE UPSTREAM

DAM IS AT THE SAME ELEVATION AS THE TOP OF

THE DOWNSTREAM DAM OR AS SPECIFICALLY

# <u> OTEXTILE INLET PROTECTION</u> (NOT TO SCALE)

SPECIFICATIONS FOR

CONSTRUCTION ENTRANCE

(NOT TO SCALE)

GEOTEXTILE SPECIFICATIONS FOR CONSTRUCTION ENTRANCE

320 PSI

TO ENCLOSE GRATE

DANDY BAG®

INSTALLATION: THE EMPTY DANDY BAG® SHOULD BE PLACED OVER THE GRATE AS THE GRATE

STANDS ON END. IF USING OPTIONAL OIL ABSORBENTS; PLACE ABSORBENT PILLOW IN POUCH, ON

THE BOTTOM (BELOW-GRADE SIDE) OF THE UNIT. ATTACH ABSORBENT PILLOW TO TETHER LOOP.

TUCK THE ENCLOSURE FLAP INSIDE TO COMPLETELY ENCLOSE THE GRATE. HOLDING THE LIFTING

MAINTENANCE: REMOVE ALL ACCUMULATED SEDIMENT AND DEBRIS FROM SURFACE AND VICINITY OF

UNIT AFTER EACH STORM EVENT. REMOVE SEDIMENT THAT HAS ACCUMULATED WITHIN THE

REMOVE AND REPLACE ABSORBENT PILLOW WHEN NEAR SATURATION.

ADS FLEX-STORM IS AN ACCEPTABLE INLET PROTECTION ALTERNATIVE.

CONTAINMENT AREA OF THE DANDY BAG® AS NEEDED. IF USING OPTIONAL OIL ABSORBENTS;

\*\* DANDY BAGS MAY ONLY BE USED FOR INLET PROTECTION WHEN THE DRAINAGE STRUCTURE IS

DEVICES (DO NOT RELY ON LIFTING DEVICES TO SUPPORT THE ENTIRE WEIGHT OF THE GRATE), PLACE

STANDARD FABRIC IS AN

ORANGE WOVEN MONO FILAMENT

FOS<0.6 MM

11X10-3 CM./SEC.

MINIMUM PUNCTURE STRENGTH | 80 PSI

MINIMUM TEAR STRENGTH

MINIMUM BURST STRENGTH

EQUIVALENT OPENING SIZE

MINIMUM ELONGATION

I PERMITTIVITY

LIFTING STRAPS

MOVEMENT OF

UNIT WITH GRATE —

ALLOW FASY

INSTALLATION AND MAINTENANCE GUIDELINES

COMPLETELY SURROUNDED BY PAVEMENT.

THE GRATE INTO ITS FRAME.

STONE SIZE-ODOT #2(1.5-2.5 INCH)

STONE SHALL BE USED, OR RECYCLED

CONSTRUCTION ENTRANCE IS PROPOSED IN

AN EXISTING PAVED AREA. THE EXISTING

PAVEMENT MAY BE UTILIZED IN LIEU OF

LENGTH-THE CONSTRUCTION ENTRANCE

SHALL BE AS LONG AS REQUIRED TO

STABILIZE HIGH TRAFFIC AREAS BUT NOT

LESS THAN 70 FT. (EXCEPTION: APPLY 30

THICKNESS-THE STONE LAYER SHALL BE AT

FT. MINIMUM TO SINGLE RESIDENCE LOTS).

LEAST 6 INCHES THICK FOR LIGHT DUTY

ENTRANCES OR AT LEAST 10 INCHES FOR

. WIDTH-THE ENTRANCE SHALL BE AT LEAST

14 FEET WIDE, BUT NOT LESS THAN THE

GEOTEXTILE—A GEOTEXTILE SHALL BE LAID

FULL WIDTH AT POINTS WHERE INGRESS OR

OVER THE ENTIRE AREA PRIOR TO PLACING

STONE. IT SHALL BE COMPOSED OF STRONG

ROT-PROOF POLYMERIC FIBERS AND MEET

THE FOLLOWING SPECIFICATIONS:

TIMING—THE CONSTRUCTION ENTRANCE

SHALL BE INSTALLED AS SOON AS IS

PRACTICABLE BEFORE MAJOR GRADING

HEAVY DUTY USE

FGRESS OCCURS

ACTIVITIES.

CONCRETE FOUNVALENT WHEN THE

7. CULVERT-A PIPE OR CUIVERT

OUT ONTO PAVED SURFACES.

8. WATER BAR-A WATER BAR SHALL BE

CONSTRUCTED AS PART OF THE

DISCONSTRUCTED UNDER THE ENTRANCE IF

FLOWING ACROSS THE ENTRANCE OR TO

PREVENT RUNOFF FROM BEING DIRECTED

CONSTRUCTION ENTRANCE IF NEEDED TO

THE LENGTH OF THE CONSTRUCTION

BY SEDIMENT CONTROLS, SHALL BE

ENTRANCE AND OUT ONTO PAVED

PREVENT SURFACE RUNOFF FROM FLOWING

. MAINTENANCE-TOP DRESSING OF ADDITIONAL

STONE SHALL BE APPLIED AS CONDITIONS

DEMAND. MUD SPILLED, DROPPED, WASHED

OR TRACKED ONTO PUBLIC ROADS, OR ANY

SURFACE WHERE RUNOFF IS NOT CHECKED

REMOVED IMMEDIATELY, REMOVAL SHALL BE

ACCOMPLISHED BY SCRAPING OR SWEEPING.

10. CONSTRUCTION ENTRANCES SHALL NOT BE

RELIED UPON TO REMOVE MUD FROM

TRACKING. VEHICLES THAT ENTER AND

11. REMOVAL-THE ENTRANCE SHALL REMAIN IN

PLACE UNTIL THE DISTURBED AREA IS

LEAVE THE CONSTRUCTION-SITE SHALL BE

VEHICLES AND PREVENT OFF-SITE

RESTRICTED FROM MUDDY AREAS.

STABILIZED OR REPLACED WITH A

PERMANENT ROADWAY OR ENTRANCE.

NEEDED TO PREVENT SURFACE WATER FROM

1.	INLET PROTECTION SHALL BE CONSTRUCTED EITHER BEFORE UPSLOPE LAND	5.	EQUIVALENT OPENING SIZE OF
	DISTURBANCE BEGINS OR BEFORE THE INLET BECOMES FUNCTIONAL.		SIEVE AND BE RESISTANT TO S IT SHALL BE STRETCHED TIGH
2.			THE FRAME AND FASTENED SE
	EXCAVATED COMPLETELY TO A DEPTH OF AT		SHALL EXTEND FROM THE TOP
3.	LEAST 18 INCHES. THE WOODEN FRAME SHALL BE		FRAME TO 18 INCHES BELOW NOTCH FLEVATION.
٥.	CONSTRUCTED OF 2-INCH BY 4-INCH	6.	BACKFILL SHALL BE PLACED A
	POSTS SHALL BE DRIVEN ONE (1 FT.)		INLET IN COMPACTED 6-INCH
	INTO THE GROUND AT FOUR CORNERS OF THE INLET AND THE TOP PORTION OF		THE EARTH IS EVEN WITH NOT ON FNDS AND TOP FLEVATION
	2-INCH BY 4-INCH FRAME ASSEMBLED	7.	
	USING THE OVERLAP JOINT SHOWN. THE		SHALL BE CONSTRUCTED IN THE
	TOP OF THE FRAME SHALL BE AT LEAST 6 INCHES BELOW ADJACENT ROADS IF PONDED		BELOW THE INLET IF THE INLET  A SDEPRESSION THE TOP OF T
	WATER WILL POSE A SAFETY HAZARD TO		SHALL BE AT LEAST 6 INCHES
	TRAFFIC.		THAN THE TOP OF THE FRAME
4.	WIRE MESH SHALL BE OF SUFFICIENT	8.	STRUCTURES IN NEED ON INLE


STRENGTH TO SUPPORT FABRIC WITH WATER


BE STRETCHED TIGHTLY AROUND THE FRAME


AND FASTENED SECURELY TO THE FRAME.


FULLY IMPOUNDED AGAINST IT IT SHALL


	NO. RECYCLE
5. GEOTEXTILE MATERIAL SHALL HAVE AN EQUIVALENT OPENING SIZE OF 20-40 SIEVE AND BE RESISTANT TO SUNLIGHT. IT SHALL BE STRETCHED TIGHTLY AROUND THE FRAME AND FASTENED SECURELY. IT SHALL EXTEND FROM THE TOP OF THE FRAME TO 18 INCHES BELOW THE INLET NOTCH ELEVATION.	
6. BACKFILL SHALL BE PLACED AROUND THE INLET IN COMPACTED 6-INCH LAYERS UNTIL THE EARTH IS EVEN WITH NOTCH ELEVATION ON ENDS AND TOP ELEVATION ON SIDES.	
7. A COMPACTED EARTH DIKE OR CHECK DAM SHALL BE CONSTRUCTED IN THE DITCH LINE BELOW THE INLET IF THE INLET IS NOT IN A SDEPRESSION.THE TOP OF THE DIKE SHALL BE AT LEAST 6 INCHES HIGHER THAN THE TOP OF THE FRAME.	NOTES:  1. TEMPORAR THE QUAN WASTE GE 2. THE WASH 3. CONCRETE
8. STRUCTURES IN NEED ON INLET PROTECTION IN PAVEMENT AREAS ARE TO USE DANDY BAGS OR FILTER SOCK TYPE INLET PROTECTION.	4. FOLLOWING























# AR **\_** AR RIDGI ROP, OCK ME ш Project Name

BID 02-26-2025

Project Issue

ABBR. SWP3 DETAILS Sheet Name

Sheet # RC Project # 24-020